				VOLUME 17 - ENGINEERING & CONSTRUCTION STANDARD		PE0030U
				200 / 600 AMP 3Ø INTERRUPTER PAD DETAIL		
Drawn:	Eng:	Appr:	Date:			Revision: 4
RN	MB	DA	9/11			Page 1 of 2


NVE DRAWING #	A	A1	B	B1	C	D	E	F	G	H	I	J	K	WEIGHT (LBS)
PE0030U INTERRUPTER PAD 200/600 AMP STOCK # 24-0691	60"	62"	72"	74"	16"	30-1/4"	12"	36"	5"	8"	39"	8"	15"	2600 CONCRETE

CONSTRUCTION NOTES

1. CONDUITS TO BE IN PROPER CONFIGURATION TO ALLOW CONDUIT SPACING AND PLUGGED PER CD0001U, SECTION 12.1.
2. 8" - 12" TYPE 2 BACKFILL TO BE COMPACTED AT 95%. SEE SECTION 5.0 OF SUB01X, VOLUME 17, SECTION 3.
3. SAND AREA TO BE COMPATED AT 90%. 12" OF SAND MUST COVER THE CONDUIT.
4. GROUND ROD (5/8" X 8' COPPER-CLAD), TO BE INSTALLED BY DEVELOPER. TELEPHONE AND CABLE TV GROUND WIRE TO BE ATTACHED BY APPLICANT.

ENGINEERING NOTES

- A. ALL FIELD CAST PADS ARE TO BE BUILT TO NVE'S SPECIFICATION - PAD01X - AND **MUST** BE INSPECTED BY NVE PRIOR TO POURING CONCRETE.
- B. DO NOT CONCRETE SHADED AREAS.

				VOLUME 17 – ENGINEERING & CONSTRUCTION STANDARD				PE0030U
				200 / 600 AMP 3Ø INTERRUPTER PAD DETAIL				
Drawn:	Eng:	Appr:	Date:					Revision: 4
RN	MB	DA	9/11					Page 2 of 2